

GKJS19DQ62

INSULATED AERIAL WORK TRUCK

19.4 m

OVERVIEW

The XCMG GKJS19DQ62 is an insulated aerial work truck from the aerial work platforms range, built for facade works, warehouse fit-out, plant maintenance, signage and lighting. Key figures: max. working height 19.4 m, max. working outreach 11.5 m, rated line voltage 35 kV. We confirm deck capacity, floor loading and charging infrastructure before dispatch.

KEY SPECIFICATIONS

Max. working height	Max. working outreach	Rated line voltage
19.4 m	**11.5 m**	**35 kV**

SPECIFICATION

Parameter	Value
Basket slewing angle	**±120 °**
Basket rated load	**280 kg**
Upper arm insulation length	**·1.5 m**
Chassis	**QL1110ANKAY**
Engine	**4HK1-TCG61**
Power	**139 kW**

TYPICAL APPLICATIONS

- facade works
- plant maintenance
- shipyards
- warehouse fit-out
- signage and lighting
- event and stadium works

Request a quotation
Specification match, landed cost and shipping plan within 24 h.

sales@xcmglouis.com
+86 516 0000 0000

Specifications are the manufacturer's published values and may change without notice. Configuration and emission standard confirmed at order.